

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

Property

RCC Contract Section	Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
RCC GROUP "A"											
A.3.2.9.01 Replace Concrete Flatwork	481170	GRADING	Erosion and possible flood	Grading	421	7th	South east of warehouse/shop	2000	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	GRADING	Flooding, soil is higher than slab	remove soils	744	Dolph	rear patio	5000	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	GRADING	Flooding, soil is higher than slab	remove soils	720	Fredricks	rear patio	5000	Sq Ft	\$ -	\$ -
A.3.2.9.01 Replace Concrete Flatwork								GRADING		481170	\$ -

A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Demo & New Concrete	Cracks	replace	701	Fredricks	Rear patio	120	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Demo & New Concrete	swale is higher than patio of	Replacement, regrading	716	Fredricks	rear patio	450	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Demo & New Concrete	cracks, spalling	Replacement	716	Fredricks	rear patio	200	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Demo & New Concrete	Cracks	Replace	714	Melissa	Rear patio	280	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Demo & New Concrete	Cracks, extreme slope. Drain	Also need to level the clothesline's.	722	Melissa	Front driveway and trash area	1000	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Saw Cut & New Concrete	spalling, cracks, flooding	replacement	221	7th	F porch. R patio, trash area, ALL concrete at unit.	1000	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Saw Cut & New Concrete	trip hazard - pipe routed through the approach.	Re-route drain pipe	309	7th	Approach from 7th street	150	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Saw Cut & New Concrete	SWALE broken (vehicle traffic)	replacement (12" thick for vehicle traffic)	421	7th	Office east driveway (100 ft)	200	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Saw Cut & New Concrete	spalling	slab replacement (access door on separate line)	421	7th	Office east driveway	120	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Saw Cut & New Concrete	Cracks, trip hazard	Replace	711	Melissa	Front walkway	80	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Saw Cut & New Concrete	Trip hazard	Replace	714	Melissa	Front driveway	27	Sq Ft		\$ -

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

Property

RCC Contract Section	Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Saw Cut & New Concrete	Cracks	Replace	715	Melissa	Front driveway and walkway	300	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Saw Cut & New Concrete	Cracks	Replace	730	Melissa	Front walkway	10	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Saw Cut & New Concrete	Trip hazard	Replacement	734	Melissa	Front walkway and trash area both addresses	700	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Saw Cut & New Concrete	Trip hazard	Replacement	746	Melissa	Trash area	500	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Saw Cut & New Concrete	Racks	Replace	738/742	Melissa	Front driveway	510	Sq Ft		\$ -
A.3.2.9.01 Replace Concrete Flatwork								SLABS		481170	\$ -
A.3.2.9.01 Replace Concrete Flatwork	481170	SLAB - Utility Access Door	spalling, cover loose	New floor door (48x60) and concrete curb	421	7th	Office east driveway	1	Each		\$ -
A.3.2.9.01 Replace Concrete Flatwork								ACCESS DOOR		481170	\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Add Course(s)	Erosion	Add 1 course of blocks	301	Collins	Driveway right side	24	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Add Course(s)	Erosion	Add 1 course	309	Collins	Front porch	24	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Add Course(s)	erosion		316	Collins	Front porch	10	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Add Course(s)	Erosion	Add 1 course of block	745	Fredricks	N/E corner close to Williams gate	40	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Add Course(s)	Erosion over top of wall	Add one course		Melissa	Melissa wall rear of collins	300	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Crack Chase & Grout	Crack chase and fill		308	Collins		45	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Crack Chase & Grout	Crack chase and fill			Dolph	Retaining wall between dolph and fredricks	200	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Crack Chase & Grout	Crack chase and tuck point	Approx 3 ft high. Qty is the entire length of the wall		Dolph	Retaining wall between Powell and dolph	198	Lin Ft		\$ -

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

Property											
RCC Contract Section	Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
A.3.2.9.03 Repair CMU Walls	481170	CMU - Crack Chase & Grout	Cracks, spalling		745	Fredricks	SE Street corner. OF FRED/MELISSA	200	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Crack Chase & Grout	Cracks	Grind, grout	715	Melissa	SE.	70	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Crack Chase & Grout	Cracks	Qty is the length of the wall		Melissa	Melissa North. Between Fredricks/Williams.	300	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Crack Chase & Grout	Cracks, spalling	Qty is the length of the wall		Melissa	Melissa Center. Between Melissa/Fredricks	300	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Crack Chase & Grout	Cracks	Grind, crack chase and fill . BOTH SIDES, qty is 2X actual length of the wall		Melissa	Melissa South, newest section of wall. Closer to melissa	500	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Crack Chase & Grout	Crack chase and fill		700	Powell		20	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Crack Chase & Grout	Crack chase & grind		716	Powell	rear	25	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Crack Chase & Grout	Crack chase & fill		720	Powell	rear patio	25	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Crack Chase & Grout	Crack chase and tuck point.	2 to 3 ft high wall, qty is the length of entire wall		Powell	Retaining wall between Powell/ melissa	270	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Demo & Replace	Erosion	Repair block wall	205	7th	Driveway	10	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Demo & Replace	Remove and replace damaged wall	Approx 3 courses	309	7th	rear @ swale area	60	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Demo & Replace	Grind		708	Dolph	rear ret wall	4	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Demo & Replace	Remove and replace retaining wall	approx 3x30	736	Dolph	between dolph/powell	90	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Demo & Replace	cut / trip hazard - old pipe	Cut pipes flush and patch		Dolph	Retaining wall between powell and dolph	10	Each		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Demo & Replace	Cracked wall	Repair	800	Fredricks	Trash area	18	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Demo & Replace	cut / trip hazard - old pipe	Cut pipe flush and patch		Fredricks	Retaining wall between dolph and fredricks	10	Each		\$ -

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

Property											
RCC Contract Section	Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
A.3.2.9.03 Repair CMU Walls	481170	CMU - Demo & Replace	Replace damaged / leaning wall	3 courses high	708	Powell	Retaining g wall	150	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Grind	Grinding and patch	poor workmanship	700	Fredricks	Retaining wall	16	Lin Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Grind	Grind smooth	Bad workmanship	716	Powell	rear wall	4	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Grind	Grind smooth	Previously bad workmanship	720	Powell	rear wall	4	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - Grind	cut / trip hazard - old pipe	Cut metal post flush and patch		Powell	Retaining wall between powell & Melissa	10	Each		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	Erosion	new retaining wall. 2 courses down to 1	221	7th	Driveway right side	60	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	erosion onto driveway	Extend retaining wall	300	Collins	At front porch	24	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	erosion onto driveway	1 more course . Stop at approach	300	Collins	left of driveway	36	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	Erosion	Extend block wall . 3X6	301	Collins	Front porch	18	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	Erosion	Extend block wall . 5 ft slop to 2 courses	301	Collins	Rear patio and storage room	50	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	erosion onto driveway	Extend retaining wall, add 1 course	308	Collins	front porch	54	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	Erosion	Extend block wall. 2 ft hi	309	Collins	Front porch	10	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	Erosion onto clothesline area	Extend r the retaining wall . 3 ft high, fade to 1 course	320	Collins	Trash area	75	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	Erosion from 723 Melissa	Extend retaining wall. 5 ft high, fade to 1 course	321	Collins	SE by trash area.	75	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	erosion	Max 4 courses, fade down to one by street	700	Fredricks		160	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	Fall hazard, wall missing. 2 places	Fill in cmu	701	Fredricks	Retaining wall at rear porch	16	Sq Ft		\$ -

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

RCC Contract Section	Property		Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
	Number	Trade Description									
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	erosion	Extend retaining wall	704	Fredricks		40	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	erosion onto driveway	Extend retaining wall	708	Fredricks		40	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	erosion onto driveway	Extend retaining wall -2 courses fade tor one	712	Fredricks		40	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	erosion onto driveway	Extend retaining wall	720	Fredricks		40	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	Erosion	Extend retaining wall . 3 ft hi	800	Fredricks	NE . CORNER OF FRED/melissa	45	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls	481170	CMU - New Wall	Erosion	Extend lock wall towards the west. 2 ft hi	800	Fredricks	Driveway and trash area	20	Sq Ft		\$ -
A.3.2.9.03 Repair CMU Walls								Total		481170	\$ -

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

RCC Contract Section	Property Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
RCC GROUP "A"											
A.3.2.9.04 Repair Concrete Stairs	481170	STEPS - Demo & Replace	Trip hazard	Masonry Repairs	301	Collins	Front porch	20	Sq Ft		\$ -
A.3.2.9.04 Repair Concrete Stairs	481170	STEPS - Demo & Replace	Trip hazard		309	Collins	Front porch	20	Sq Ft		\$ -
A.3.2.9.04 Repair Concrete Stairs	481170	STEPS - Demo & Replace	Saw it and replace step	Front walk	700	Powell	front walk	15	Sq Ft		\$ -
A.3.2.9.04 Repair Concrete Stairs	481170	STEPS - New Concrete	Fall hazard. Approximately 2 foot drop	New steps. New slab. New handrail by others	705	Fredricks	Rear patio	80	Sq Ft		\$ -
A.3.2.9.04 Repair Concrete Stairs	481170	STEPS - New Concrete	Rear patio, approx 2 ft drop off	New steps, new slab, new handrail by others	717	Fredricks	Rear patio	80	Sq Ft		\$ -
A.3.2.9.04 Repair Concrete Stairs								Total		481170	\$ -

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

RCC Contract Section	Property Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
RCC GROUP "B"											
B.3.2.9.02 Deseret Patio Slabs	481173	SLAB - Demo & New Concrete			1050	Deseret	#14 (Rear)	400	Sq Ft		\$ -
B.3.2.9.02 Deseret Patio Slabs	481173	SLAB - Demo & New Concrete			1050	Deseret	#15 (rear)	400	Sq Ft		\$ -
B.3.2.9.02 Deseret Patio Slabs	481173	SLAB - Saw Cut & New Concrete			1050	Deseret	#4 Front Entry Landing & Walkway	80	Sq Ft		\$ -
B.3.2.9.02 Deseret Patio Slabs								Total		481173	\$ -

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

RCC Contract Section	Property Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
RCC GROUP "C"											
C.3.2.2 Regrade/Direct Water Away from Units	481172	GRADING	Erosion and flooding	Regrade area away from slab	920	Bighorn	Clothesline slab	450	Sq Ft		\$ -
C.3.2.2 Regrade/Direct Water Away from Units	481172	GRADING	Erosion and flooding	Grading	936	Bighorn	Clothesline area	500	Sq Ft		\$ -
C.3.2.2 Regrade/Direct Water Away from Units	481172	GRADING	Erosion into Catch basin	Move soils away from grate	2001	Lassen	Northeast corner near intersection of Muriel and rimrock	500	Sq Ft		\$ -
C.3.2.2 Regrade/Direct Water Away from Units	481172	GRADING	Flooding	Regrade Away from Units	900	Zion	900-920 Zion	5000	Sq Ft		\$ -
C.3.2.2 Regrade/Direct Water Away from Units	481172	GRADING	Flooding	Grading	912	Zion	Front yard north west corner	300	Sq Ft		\$ -
C.3.2.2 Regrade/Direct Water Away from Units	481172	GRADING	Erosion, flooding		932	Zion	Southwest corner by laundry room	500	Sq Ft		\$ -
C.3.2.2 Regrade/Direct Water Away from Units	481172	GRADING	Flooding		940	Zion	Rear patio	500	Sq Ft		\$ -
C.3.2.2 Regrade/Direct Water Away from Units								BIGHORN		481172	\$ -
RCC GROUP "C"											
C.3.2.2 Regrade/Direct Water Away from Units	481174	GRADING	Ponding, drainage issue		1921	Yosemite	Driveway	500	Sq Ft		\$ -
C.3.2.2 Regrade/Direct Water Away from Units	481174	GRADING	driveway ponding at center	needs grading towards the north from low point in driveway	1929	Yosemite	Front driveway	750	Sq Ft		\$ -
C.3.2.2 Regrade/Direct Water Away from Units								YOSEMITE		481174	\$ -

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

RCC Contract Section	Property Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
RCC GROUP "C"											
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Demo & New Concrete	Cracks drainage problem erosion trip hazard spalling	Replace. Need to move the mailboxes. Need core drill at north wall	921	Bighorn	North side of building @ garage	2800	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Demo & New Concrete	Cracks	Replace	917	Lassen	Carport	210	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Demo & New Concrete	Severe spalling slab drains to her house	Replace	2004/2008	Lassen	slab under swap coolers	792	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Demo & New Concrete	Cracked, trip hazard, flooding	Replacement	900	Zion	Rear patio	405	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Demo & New Concrete	Flooding, cracks	Replacement	904	Zion	Rear patio	400	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Demo & New Concrete	Erosion, trip hazard,	Replacement	913	Zion	Clothesline slab	225	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Demo Only	Walkway to no where	Demo. DO NOT REPLACE	921	Bighorn	Southeast corner	70	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Demo Only	Cracks, trip,	Demo DO NOT REPLACE	932	Lassen	Old clothes line area	144	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - New Concrete	Move mailboxes outside of fence	New slab	921	Bighorn	South west side of building. Southeast side parking lot	240	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - New Concrete	Hole	Patch	913	Lassen	Slab at laundry room	1	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - New Concrete	Flooding	new swale @ new CMU wall	900	Zion	East Prop Line @ Field	150	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - New Concrete	Flooding	Sew slab at rear	904	Zion	rear patio	200	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - New Concrete	Flooding	New swale. 3 ft wide 300 ft long	904-920	Zion	South property line behind Zion	900	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Saw Cut & New Concrete	Trip hazard	Replace		Bighorn	Basketball court	49	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Saw Cut & New Concrete	Trip	Replace		Lassen	Walkway from Lassen to playground	225	Sq Ft		\$ -

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

Property											
RCC Contract Section	Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Saw Cut & New Concrete	Cracks	Replace		Lassen	Walkway from Lassen to playground	16	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Saw Cut & New Concrete	Trip	grind. Remove fenc post.	2017	Monterey	North east near trash area	4	Lin Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Saw Cut & New Concrete	Spauling	Replacement	901	Zion	Rear patio	120	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Saw Cut & New Concrete	Severe spalling, trip hazards, erosion	Replacement , remove clothesline frame	903	Zion	Rear patio	240	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Saw Cut & New Concrete	Drainage swale is broken and does not drain	Replacement 3 ft wide	920	Zion	South of building rear yard	36	Lin Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Saw Cut & New Concrete	Cracks, poor drainage, TripAdvisor,	Replacement	937	Zion	Clothesline slab	225	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481172	SLAB - Saw Cut & New Concrete	Trip and cracks	Replacement	945	Zion	Front porch	30	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios								BIGHORN	481172	\$	-

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

Property

RCC Contract Section	Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
RCC GROUP "C"											
C.3.2.9.01 Replace Sidewalks, Patios	481174	SLAB - Demo & New Concrete	Tree lifting the slab	Replacement	1901	Yosemite	Rear patio	405	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481174	SLAB - Demo & New Concrete	Tree damaging slab	350 Replacement	1908	Yosemite	Rear patio	350	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481174	SLAB - Demo & New Concrete	Ponding drainage from severe cracking	Complete replacement	1928	Yosemite	Front driveway	600	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481174	SLAB - Demo & New Concrete	Cracks, bonding, drainage issues	Replacement	1929	Yosemite	Front driveway	372	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481174	SLAB - New Concrete	Slab is completely missing		1917	Yosemite	Rear clothesline area	100	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481174	SLAB - Saw Cut & New Concrete	Cracks and tree roots	Replacement	1905	Yosemite	Walkway from front door to fire hydrant	16	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481174	SLAB - Saw Cut & New Concrete	Cracks	Replace	1905	Yosemite	Middle of driveway between 05 and 09	80	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481174	SLAB - Saw Cut & New Concrete	Severe misalignment trip hazard	Replacement	1920	Yosemite	Clothesline slab	180	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481174	SLAB - Saw Cut & New Concrete	Drainage swale cracked cracked	Replacement	1920	Yosemite	Western property line	100	Sq Ft		\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481174	SLAB - Saw Cut & New Concrete	Tree pushing up slab	Tree pushing up slab. Severe spalling	1932	Yosemite	Rear patio	500	Sq Ft		\$ -
								C.3.2.9.01 Replace Sidewalks, Patios	YOSEMITE	481174	\$ -
C.3.2.9.01 Replace Sidewalks, Patios	481174	SLAB - Utility Access Door	Water main vault lid trip hazard	New floor door (48x72) and concrete frame	1929	Yosemite	On rim rock road	1	Each		\$ -
								C.3.2.9.01 Replace Sidewalks, Patios	ACCESS DOOR	481174	\$ -

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

RCC Contract Section	Property Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
RCC GROUP "C"											
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Add Course(s)	Erosion	Add two courses to retaining wall	900	Bighorn	Northwest corner	24	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Add Course(s)	Erosion	Add one course to retaining wall	902	Bighorn	East side	45	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Add Course(s)	Erosion	Add on course	937	Bighorn	Retaining wall between units	45	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Add Course(s)	Flooding wash overflows	Add two courses to the top of the existing wall wall		Zion	South property line behind Zion next to the wash	600	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Crack Chase & Grout	Crack in CMU wall	Grout	2008	Bighorn	Clothesline area . East property line	8	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Crack Chase & Grout	Cracks in cmu	Grout	2012	Bighorn	Western property line	5	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Crack Chase & Grout	Cracks in wall	Grout	2020	Bighorn	West property line	5	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Crack Chase & Grout	Retaining wall damage	Grout		Bighorn	Basketball court	100	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Crack Chase & Grout	cracks	Grout		Bighorn	Retaining wall between Big Horn Zion.300 ft long x 5ft high	300	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Crack Chase & Grout	Cracks	Grout	936	Lassen	Clothesline slab	24	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Crack Chase & Grout	Cracks		900	Zion	retaining wall between Monterey and Bighorn	20	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Crack Chase & Grout	Cracks	Grout			South property line behind Zion	840	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Crack Chase & Grout	Cracks	Grout			East prop line Muriel south of Zion	108	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Crack Chase & Grout	Cracks	Grout			North property line on Rimrock	885	Lin Ft		\$ -

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

Property											
RCC Contract Section	Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Crack Chase & Grout	CMU wall damage	Grout			East Prop Line.Muriel Street between Big Horn and Zlon	230	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Crack Chase & Grout	Cracks, broken blocks	more photos.			East Prop Line.Muriel Street between Big Horn and Zlon				\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Crack Chase & Grout	Cracks				East Prop Line. Muriel From Bighorn to Rimrock	350			\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Demo & Replace	Retaining wall damage . 2 courses	Replacement		Lassen	Basketball court	40	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Demo & Replace	Missing block		916	Zion	South west corner	4	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - Demo & Replace	Retaining wall is too high kids jump on the house next-door	Remove two courses of block	920	Zion	West	60	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - New Wall	Erosion	Extend existing retaining wall three courses	937	Bighorn	Clothes line area	30	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - New Wall	Erosion	New retaining wall . 3 courses	2008	Bighorn	Clothesline area	72	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - New Wall	Erosion	New retaining wall . 4 ft	2012	Lassen	Clothes line area	200	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - New Wall	Flooding	new block wall & swale	900	Zion	Western propert border next to field	300	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - New Wall	Erosion and flooding	Extend retaining wall. 3 courses, fade to one	904	Zion	South west of laundry room	30	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - New Wall	Erosion	Extend retaining wall, three courses	907	Zion	North west near clothes lines	36	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - New Wall	Erosion and flooding	Extend existing retaining wall for course or courses feet down to one	908	Zion	South west of building	48	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - New Wall	Erosion	Extend retaining wall around the corner of the slab . 3 courses	912	Zion	Clothesline slab	75	Sq Ft		\$ -

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

RCC Contract Section	Property Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - New Wall	Erosion and flooding flooding	Extend retaining wall three courses feed to one	912	Zion	North west corner	30	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - New Wall	Erosion and flooding	Extend retaining wall three courses feet down to two	912	Zion	South west corner of building	36	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - New Wall	Erosion	Extend retaining wall three courses hi	913	Zion	North west corner by clotheslines	24	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - New Wall	Erosion	Extend the retaining wall cut down tree	917	Zion	North west corner clothes line area	36	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481172	CMU - New Wall	Erosion	New wall 5 courses, fade to one	921	Zion	Southeast corner near the pedestrian walkway	150	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs								BIGHORN	481174	\$	-

TASK LIST - PC1095 Concrete Replacement, Barstow RAD Rehab

Property

RCC Contract Section	Number	Trade Description	Deficiency	Solution	Address #	Street	Location Notes	Qty	Unit	Unit Cost	Subtotals
RCC GROUP "C"											
C.3.2.9.03 Fencing CMU Repairs	481174	CMU - Crack Chase & Grout	Cracked CMU		1909	Yosemite	Driveway	20	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481174	CMU - Crack Chase & Grout	wall cracks		1913	Yosemite	Right side of driveway	60	Lin Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481174	CMU - Demo & Replace	Retaining wall broken	Connect the 2 sections together	1916	Yosemite	North side of driveway	16	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481174	CMU - New Wall	Erosion	Extend retaining wall. 4x16	1920	Yosemite	Southwest retaining wall	64	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481174	CMU - New Wall	Erosion	Extend retaining wall . 4x16	1921	Yosemite	Clothes line area	64	Sq Ft		\$ -
C.3.2.9.03 Fencing CMU Repairs	481174	CMU - New Wall	Erosion	Extend retaining wall . 4x16	1928	Yosemite	South west retaining wall	64	Sq Ft		\$ -

C.3.2.9.03 Fencing CMU Repairs **YOSEMITE** **481174** \$ -

SUBTOTAL \$ -

PERMITS

TOTAL CONTRACT PRICE \$ -